

ABBREV.	ITEM DESCRIPTION
AL	ALARM LIGHT
AM	AMP METER
CCB	CONTROL CIRCUIT BREAKER SQUARE D
DR	DUPLEX RECEPTACLE / G.F.I.
DRB	DUPLEX RECEPTACLE BREAKER SQUARE D
ECB	EMERGENCY CIRCUIT BREAKER SQUARE D
ETM	ELAPSE TIME METER TO NO LESS THAN TENTHS OF A SECOND
F	FUSE
FL	FLASHER
FR	FLOAT REGULATOR ROTO FLOAT
G	GROUND
GR	GENERATOR RECEPTACLE (SEE DETAIL. S-9)
HOA	HAND-OFF-AUTO-SELECTOR SQUARE D
MB	MOTOR BREAKER SQUARE D
MCB	MAIN CIRCUIT BREAKER SQUARE D
LA	LIGHTNING ARRESTOR (TO BE MOUNTED OUTSIDE OF DISCONNECT)
MS	MOTOR STARTER SQUARE D
N	NEUTRAL
OL	OVERLOAD HEATER SQUARE D
PA	POWER AVAILABLE LIGHT (3 REQUIRED, 1 EACH PHASE)
PB	PUSH BUTTON (1,2,3,4,5,6) AMP METERS 1&2
PM	PHASE MONITOR
RL	RUN INDICATOR
RLY	RELAY 24 VOLTS DC WITH TEST BUTTON
RTS	REGULATOR TERMINAL STRIP (16 CONNECTIONS)
RTU	RADIO TELEMETRY UNIT CIRCUIT BREAKER SQUARE D
SLS	SELECTOR SWITCH FOR OVERHEAD HPS DUSK DAWN LIGHT
TS	TERMINAL STRIP
TTS	THERMAL TERMINAL STRIP

CITY OF PALM BAY, UTILITIES DEPARTMENT  
POLICIES, PROCEDURES AND STANDARDS  
INSTALLATION DETAIL

**PUMP STATION**  
**CONTROL PANEL LEDGER**

DWN.BY: M.K.L.	DATE: 1-1-08
REV. E.K.R.	DWG. NO.
2-3-10	<b>LS-9</b>